

## Case story Stingray SBT-170 XL



Customer:	Billerud Korsnäs Gruvöns Mill
Installed:	2011
Position:	Fibersludge with pins.
Performance:	
Q normal:	80 m <sup>3</sup> /hour
Q maximal:	120 m <sup>3</sup> / hour
DS Inlet:	0,3 – 1,0 %
DS out:	10 – 15%
Removal:	96-98% > 500 micron (wire opening)